


**UNIVERSITY OF TOLEDO
FACILITIES AND CONSTRUCTION**

Section:	Electrical/Electronics	Procedure Number:	E-07
Subject:	Breaker Operational Tests at the UT HSC Main Sub-Station	Effective Date:	January 1980
		Revised Date:	December 2019
Facilities Officer:		Reviewed Date:	December 2019

Standard Operating Procedure

Attached is a copy of the procedure that the Toledo Edison Load Dispatcher will follow when breaker operations tests are performed at the main sub-station.

Purpose

To ensure reliability of main electrical breaker at UT sub-station.

Procedure

The tests are done on a four (4) year cycle at the Toledo Edison systems with regards to transmission. The same schedule would apply to the transmission breakers at the University of Toledo.

Prior to the actual switching, the Load Dispatcher will arrange with the Electrical Manager or a designated alternate, a time and date on which to perform these tests.

A separate copy of the procedures shall be left in the breaker control house so it can be available for the Toledo Edison and UT personnel to follow.